

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Gogebic COUNTY
T 47N R 42W

DESCRIPTION OF CORNER Section Corner 20, 21, 28, and 29

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED June 16, 1971

WITNESSES TO CORNER..... Sugar Maple 8 S41°W (mag.) 3.3 ft. "S29, NBT"



Sugar Maple 6 N16°E (mag.) 7.1 ft. "S21, NBT"

Sugar Maple 6 N42°W (mag.) 6.3 ft. "S20, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 2"x2" square, sawn stake at corner, probably a K-C Corp. C.F.I. marker.

Corner placed from a maple stub corresponding to an original BT, Sugar 7 S85W 6, rotted, but with old axe marks and bark overgrowth suggesting witness faces. Found a U.S.F.S. location tag dating to 1940's at corner. Position fits well with stream crossings to W, E, and N (2), and measures consistently to other known corners around Sec. 20.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

June 21, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68