


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Gogebic COUNTY
T 47N R 42W

DESCRIPTION OF CORNER Section Corner 19, 20, 29, and 30
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED June 4, 1971
WITNESSES TO CORNER..... Y. Birch 5 S45°E (mag.) 24.8 ft. "S29, NBT"



Balsam 8 S85°W (mag.) 4.8 ft. "S30, NBT"
W. Spruce 9 N48°W (mag.) 19.3 ft. "S19, NBT"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established at record bearing and distance from a yellow birch stump believed to be the original BT, but too badly rotted to have preserved any identifying marks. Found evidence of a tree having once stood in position of hemlock BT, but could make no positive species identification. Distance south to a stream agrees reasonably well, although thread of stream is now somewhat obscured by beaver flooding. Distances to corners 1/2 mile N and 1 mile E are consistent with other corners and distances around Section 20. Found a U.S.F.S. location tag on a hemlock tree 21 ft. West of corner.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE June 21, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68