

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Gogebic COUNTY
T 47N R 42W

DESCRIPTION OF CORNER Meander Corner between Sections 20 & 21

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 5, 1971

WITNESSES TO CORNER..... Cedar 14 S38°W 38.8 ft. "MC, NBT"



Hemlock 6 S68°E 5.9 ft. "MC, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner replaced at true original record bearing and distance from a monument purporting to be, and accepted as, the M.C. between Sec. 17 & 20, said monument bearing N63°W 2.46 chains from M.C. described herein. The bearing and distance used appears to fit the shoreline very well, and was considered the most practicable way in which to re-locate the corner.

Corner is within boundary of Lake Gogebic State Park.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

June 21, 1972

Arthur O. Enger

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68