

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Gogebic COUNTY  
T 47N R 42W

DESCRIPTION OF CORNER Meander Corner between Sections 21 and 28

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 5, 1971

WITNESSES TO CORNER..... North Corner of cottage foundation on Lot 8, S6°W 87.63 ft.



North corner of cottage-garage foundation beam on Lot 9,  
S61°W 57.00 ft.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner replaced as nearly as possible in conformity with position indicated on Lieberthal Plat (L. 2 of Plats, P.22), on Lot 9 near its SE'ly corner. The position conforms well with the direction of the south line of Sec. 20 extended E'ly to the shore of Lake Gogebic, and is compatible with measured distances between corners found around the perimeter of Sec. 20. On the Lieberthal Plat, the spatial relationship of this corner to plat or other corners is not shown, but the undersigned measured from a monument purporting to be M.C. between Sec. 27 & 28, finding a true bearing and distance of N54°06'W 811.1 ft., which is fairly conformable to the original meander line notes.

(Corner pipe buried about 6 inches below ground surface.)

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE June 21, 1972

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68