

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE Register's Office } ss.
Filing Requirement of Act 74, Mich. P.A. 1970 Gogebic County }

For corners in

ONTONAGON

Located in:

Corner Code #

(County)

GOGEBIC

1. Public Land Survey

T48N R 41W	B - 13
T47N R 41W	B - 13
T R	
T R	
S T R	
S T R	
S T R	
S T R	

2. Property Controlling

in Section

3. Miscellaneous

Property in Sec.

Received for record the
10TH day of NOVEMBER
A. D. 1999 at 10:25 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 269
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1/4 Corner common to Sections 6 & 31, T47-48N, R41W.

I, Earl W. Applekamp, in a field survey on Sept. 29, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1	●											
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13	●											

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by William A. Burt, U.S. Deputy Surveyor in 1847. Set Cedar Post.

ORIGINAL BEARING TREES:

12" Cedar N30°E 5 Links (3.30 feet)
20" Hemlock N62°W 15 Links (9.90 feet)

DEED GROUP APPROVED
Earl W. Applekamp
COUNTY REMONUMENTATION
10-14-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. I found a 4"x4" metal yellow tag 18 feet North of the position I set the corner. The tag was scribed 4 feet South to approximate corner. I re-established the corner by single proportionate measure and on the Town line between the monumented SW Corner of Section 31, and the S 1/4 Corner of Section 32. These two corners had been monumented from original bearing trees in 1961 and 1970 respectively.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2"x30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T47N, T48N, R41W, 1/4, S6, S31, 1999, P.S. 17610. I established 3 bearing trees and a reference object.

Nail in 7" Maple N01°E 20.53' - Nail in 7" Maple S27°E 18.40'
Nail in 7" Maple Due East 46.55' - 6' Steel Sign Post Due West 0.76'



Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date September 29, 1999