

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
22<sup>ND</sup> day of OCTOBER  
A. D. 1999 at 11:20 o'clock  
A. M., and recorded in  
Liber 7 of CORNERS

on page 256  
Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

SECTION

GOGEBIC  
(County)

Located in:

Corner Code #

Seq. 1

- 1. Public Land Survey      T 47NR 41W      E-1
- T    R                    \_\_\_\_\_
- T    R                    \_\_\_\_\_
- T    R                    \_\_\_\_\_
- T    R                    \_\_\_\_\_
- 2. Property Controlling    S    T    R                    \_\_\_\_\_
- in Section                S    T    R                    \_\_\_\_\_
- 3. Miscellaneous            S    T    R                    \_\_\_\_\_
- Property in Sec.         S    T    R                    \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Section Corner common to Sections 32 & 33, T48N R41W &  
Sections 4 & 5, T47N R41W.

I, Earl W. Applekamp, in a field survey on Sept. 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORRECTION: SEE LIBER 7, PAGE 272

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by William A. Burt, U.S. Deputy Surveyor, June 1851. Set Cedar Post.

ORIGINAL BEARING TREES:

- 14" Hemlock                N35°E                2.64 feet
- 14" Hemlock                N65°W                11.88 feet

BEEN GROUP APPROVED  
Richard L. Dehn 10/14/99  
COUNTY RE-MONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original bearing trees were found. The only original evidence found was a leave swamp call on the original field notes, which state, going West on bottom of Section 33; leave swamp 79.00 chains. Corner was set at 80.00 chains. Corner was re-established by single proportionate measure and on line between opposite Section Corners on the Township line. This location is in agreement with the swamp call indicated above.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2"x30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N, 47N R41W, S32, S33, S4, S5, 1999, P.S. 17610. I established three bearing trees and a Steel Sign Post.

- Nail in 7" Maple            N59°W    24.91' - Nail in 5" Maple    S05°W    53.20'
- Nail in 10" Maple        N30°E    40.30' - 6' Steel Sign Post    South 0.73'



Signed by Earl W. Applekamp  
Surveyor's Michigan License No. 17610

Date September 17, 1999