

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON

(County)

GOGEBIC

1. Public Land Survey

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

Located in:

Corner Code #

	T48NR 41W	F-13
	<u>T47NR 41W</u>	<u>F-1</u>
T	R	
T	R	
S	T	R
S	T	R
S	T	R
S	T	R

Register's Office }
Gogebic County } ss.

Received for record the
10th day of NOVEMBER
A. D. 1999...at 11:25 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 273
Barbara Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 Corner common to Sections 4 & 33, T47-48N, R41W.

Earl W. Applekamp, in a field survey on Oct. 01, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William A. Burt, U.S. Deputy Surveyor in 1847. Set Cedar Post.

ORIGINAL BEARING TREES:

Hemlock	20"	N04°E	23 Links (15.18 feet)
Sugar	12"	N60°W	18 Links (11.88 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. The SE 1/4 of Section 33 has been farmed for 60 + years. A fence was found running North and South 75 feet East of the calculated corner position. This fence was installed about 30 years ago by the present owner. Checking the fence 1/4 mile North there is an obvious deflection to the East. I met with the owner of the SE 1/4 and pointed this out to him. Corner was re-established about 75 feet West of the existing fence line. Corner was set by single proportionate measure and on the Town Line between the monumented South 1/4 Corner of Section 32 and the Southeast Corner of Section 33.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

At the corner position I set a 2 1/2" x 30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N, T47N, R41W, S4, S33, 1/4, 1999, P.S. 17610. I established three bearing trees and a reference object.

Nail in 7" Aspen	N76°W	56.14'	-	Nail in 10" White Birch	S81°E	78.51'
Nail in 16" Aspen	N03°E	74.23'	-	6' Steel Sign Post	South	0.66'

BREER GROUP APPROVED
Earl W. Applekamp
COUNTY REGISTER OF DEEDS
10-14-99



Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date October 4, 1999