

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

GOGEBIC

(County)

Located In:

Corner Code #

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

T48N R41W	G-13	ONTONAGON Co.
T47N R41W	G-1	GOGEBIC Co.
T R		
T R		
S T R		
S T R		
S T R		
S T R		

Received for record the
30th day of AUGUST
A. D. 1999 at 10:10 o'clock
A. m., and recorded in
Liber 7 of CORNERS
on page 243
Remona Collins Dep.
Register of Deeds

Register of Deeds Stamp & File Number

Section Corner common to Sections 33 & 34, T48N R41W and Sections 3 & 4, T47N R41W.
I, Earl W. Applekamp, in a field survey on Aug. 10 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

DEED GROUP APPROVED
Richard R. Dredin 8/24/99
COUNTY REPRESENTATIVE

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by William A. Burt, U.S. Deputy surveyor, July 17, 1851. Set Cedar Post.

ORIGINAL BEARING TREES:

10" Hemlock	N38°E	9.24 feet
12" Fir	N32°W	15.18 feet

ONTONAGON COUNTY
DEED APPROVED
Earl W Applekamp
Co-REP
8-24-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. A county road would have removed any. At the apparent corner position I found a 1/2" pipe 12" below top of a gravel road. This position agrees with a fence running East and West dividing occupied land. The owner in Section 34 indicated his fence was on the line. The owner in Section 33 has lived there for 30 years and knew of the 1/2" pipe. The position is in agreement with the original field notes. I accepted the 1/2" pipe as the corner position and monumented the corner.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x12" rebar with a 3" cap 4" below top of ground. Cap is stamped o read: County Remonumentation, T47N, T48N, R41W, S33, S34, S3, S4, 1999, P.S. 17610. I established a reference monument a 2 1/2"x30 Split base aluminum pipe with a 3" cap stamped the same as above, adding R.M. I also established three other bearing objects.

REF. MON.	N87°W	35.93'	-	P. Pole	N41°W	37.61'
Nail in 8" Spruce	S47°W	69.96'	-	Nail in 8" Aspen	S45°E	92.38'



Signed by Earl W Applekamp
Surveyor's Michigan License No. 17610

Date August 16, 1999