

SURVEY & REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>47N</u> R <u>44W</u>	M-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>47N</u> R <u>43W</u>	A-2
	S _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received for record the
14th day of MAY
A. D. 1998 at 3:20 o'clock
P m., and recorded in
Liber 6 of CORNERS
page 382
Deanna Collins Dep.
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner 1 & 6; T.47 N., R.43-44 W.

I, Richard L. Drahn in a field survey on April 29, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1. and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/10/1847. Original B.T.s --- W. Pine 36" S.16 E. 14 links (9.24') --- Y. Birch 16" N.42 W. 27 links (17.82') ---

Corner restored by Richard L. Drahn (21564) on 8/5/81, from the stump remains of the two original B.T.s. He set a 2" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following new B.T.s:

9"	Hemlock	N.09 E.	34.39'
14"	Cedar	S.30 E.	26.73'
9"	Cedar	S.79 W.	30.35'
6'	Steel sign rail	S.47 W.	2.1'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County Liber 2, Page 252 on 3/10/82.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing tree as follows:

12"	Hemlock	N.10 E.	34.28'	(new nail)
17"	Cedar	S.28 E.	27.02'	" "
10"	Cedar	S.80 W.	30.55'	" "
6'	Steel sign rail	S.59 W.	2.26'	

The stumps from the original bearing trees still remain intact.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

12"	Cedar	N.64 W.	8.68'
-----	-------	---------	-------

PEER GROUP APPROVED
Richard L. Drahn 5/13/98
COUNTY REGISTER



Signed by Richard L. Drahn

Date May 3, 1998

Surveyor's Michigan License No. 21564