

SURVEY & REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey

<u>T47NR 43W</u>	<u>A-9</u>
T47NR 44W	M-9
T R	
T R	
S T R	
S T R	
S T R	
S T R	

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

Received for record the
23rd day of JULY
A. D. 1998 at 11:40 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 31
Famora Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section corner common to sec's. 24, 25, 19, 30, T47N R.43-44 W.

I, John P. Goss, in a field survey on July 21, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

PEER GROUP APPROVED

Richard L. Drain 7/22/98
COURT ESTABLISHING

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, U.S. Deputy Surveyor, in 1847.

Original bearing trees: Lynn 16" S 41° W 30 links
Sugar Maple 12" N 51° E 27 links
Sugar Maple 30" S 30° E 27 links

On June 16, 1971, Donald D. Lappala, RLS, USFS, restored corner position at record bearing and distance from the remains of the 3 original bearing trees and natural feature ties. He set a 2½" I.D. galv. iron pipe with 3" circular bronze tablet which reads: T.47 N., R.43-44 W.; S-24, S-25, S-19, S-30; R.L.S. 12585; 1971, from which he established the following reference objects:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6" Elm (down)-N 20° W-34.1'; 10" Y. Birch (stump)-N55°E-22.8'; 13"Y. Birch(stub) S 39°E- 18.8'; 4"x4" Cedar sign post (down)- S 89° E - 2.0'
P.Strand & J. Dahlbacka on 10-17-86 added the following reference:
8" S. Maple - N 51° W- 10.78'; 10" S. Maple - N 32° W - 26.13'
4" S. Maple - N 05° W - 20.16'

D. Lappala recorded said corner in U.S.F.S. Liber R-25 on August 10, 1972. Found Lappala witnesses and monument and the other 3 witnesses.

I updated the monument and accessories as noted below to state and county specification.

Act 74 research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the monument I established the following existing and new reference objects:

9" Sugar Maple N 51° W 10.78'
12" Sugar Maple S 32° W 26.13'
5" Sugar Maple N 05° W 20.16'
10" Maple N 73° E 17.19'
6' Rail & sign Due S. 2.038 to face

(All measurement taken to nail in side of tree)



Signed by John P. Goss

Date July 21, 1998

Surveyor's Michigan License No. 23509

U.S.F.S. No. R-25