

SURVEY & REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register of Deeds }
Gogebic County } ss.

For corners in

Gogebic
(County)

Located In: Corner Code #

- 1. Public Land Survey T.47NR 43W A-11
T.47NR 44W M-11
T___R___
T___R___
- 2. Property Controlling in Section S___T___R___
S___T___R___
- 3. Miscellaneous Property in Sec. S___T___R___
S___T___R___

Received for record the
20th day of AUGUST
A. D. 1998 at 1:20 o'clock
P m., and recorded in
Liber 7 of CORNERS
on page 47
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section corner common to Sections 25, 36, 30 & 31

I, John P. Goss, in a field survey on July 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
Corner established by Austin Burt, U.S. Deputy Surveyor, in 1847.
Original bearing trees: Y. Birch 7" S 56° E 17 links } Austin Burt's B.T.
S. Maple 12" N 67° W 38 links }
S. Maple 10" N 67° E 17 links } William Burt's B.T.
Y. Birch 30" S 58° E 17 links }

On June 5, 1971, Donald D. Lappala, RLS, USFS, restored corner position at record bearing and distance from the remains of the original bearing trees: He set a 2 1/2" I.D. Iron pipe with 3" Circular bronze tablet which reads: T.47 N., R.43-44 W.; S-25, S-36, S-30, S-31; R.L.S. 12585; 1971. He established the

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: following reference objects
6" Sugar Maple S 81° E 39.2'; 8" Sugar Maple S 35° E 29.7'
4" Yellow Birch S 05° W 25.8' (down); 4"x4" Cedar sign Post N 58° E 3.5' (down)
In 1985 a 5" Sugar Maple S 10° E 38.4' was added.
He recorded said corner in Forest Service Liber V-25 on August 10, 1972.
Found Monument and witnesses trees.

I updated the monument and accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVAL
Richard P. Dealm 8/19/98
REGISTERED LAND SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From found monument I established the following existing and new reference objects:

- 8" Sugar Maple S 81° E 39.22'
 - 9" Sugar Maple S 35° E 29.86'
 - 8" Hemlock N 44° W 27.65'
 - 6" Sugar Maple S 10° E 38.24'
 - 6' Rail & Sign Due S. 1.96' to face
- (All measurements are taken to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date July 29, 1998

U.S.F.S. No. V-25