

DEC 15 1998

47-43

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } sa.

For corners in

Gogebic
(County)

Located In: Corner Code #

- 1. Public Land Survey T.47N R.43W A-12
T.47N R.44W M-12
T R
T R
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

Received for record the
17th day of SEPTEMBER
A. D. 1998 at 1:15 o'clock
P m., and recorded in
Liber 7 of CORNERS
on page 53
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Quarter section corner common to Sec's. 31 & 36
T.47 N. R.43-44 W.

I, John P. Goss, in a field survey on Sept. 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
Corner established by Austin Burt, U.S. Deputy Surveyor, in 1847.
Original bearing trees: Sugar Maple 12" S 67°30' W 14 links
Yellow Birch 14" N 50°30' E 38 links

On June 4, 1971, Donald D. Lappala, R.L.S., USFS, restored corner position at record bearing and distance from the remains of the two bearing trees and natural features ties. He set a 2 1/2" I.D. iron pipe with 3" circular bronze tablet which reads: T.47 N., R.43-44 W.: 1/4; S-31, S-36; R.L.S. 12585; 1971; from which he established the following reference objects: 10" S. Maple - N 25° E - 26.8'; 8" S. Maple - S 52° E - 13.7'; 7" S. Maple - S 75° W - 16.0'; 4"x4" Cedar sign

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: post-S 55° E - 2.4'
He recorded said corner in U.S. Forest Service Liber X-25 on August 10, 1972.
Found D. Lappala monument and reference objects.

I updated the monument and accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED

Richard R. Dealm 9/16/98
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From the found monument I established the following existing and new reference objects:

- 12" Sugar Maple N 25° E 26.88'
- 9" Sugar Maple S 52° E 13.75'
- 9" Sugar Maple S 75° W 15.81'
- 4"x4" Cedar sign post S 55° E 2.34' to face
- 6' Rail & sign Due North 1.84' to face

(All measurements taken to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509
U.S.F.S. No. X-25

Date Sept. 1, 1998