

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>43W</u>	<u>L-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	<u>T47N R 43W</u>	<u>L-13</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received for record the
10TH day of JUNE
A. D. 1999 at 10:10 o'clock
A m., and recorded in
Libr 7 of CORNERS
on page 163
Karrena Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____ 5.
Private Claims _____
Quarter corner 1 & 36; T.46-47 N., R.43 W.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	13		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Richard L. Drahn, in a field survey on May 18, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original corner established by John Burt on 8/7/1847. Original bearing trees:
Sugar 10" S.69° E. 40 links (26.40')
Sugar 16" N.54° W. 12 links (7.92')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Restored corner position at record bearing and distance from the remains of the two original bearing trees. The first is a very large hole (species undetermined). The second one is now a large Sugar Maple decayed to well below ground line. The 5.00 chain distance east to "descend hill gradually to post), although indistinct, checks. The "feldspar in ledge 20", 6.00 chains west of the corner is not a valid call. No ledge outcrops is evident in any direction from the call for at least eight chains. The 40.00 chain distance east and west to recovered corners is in accord with the field notes of the original Government Survey.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
At the corner position I set a 2" x 30" aluminum pipe monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree):

- Sugar Maple 11" N.28° W. 46.16'
- Sugar Maple 11" S.61° E. 17.98'
- Sugar Maple 5" S.35° W. 20.88'
- Steel sign rail 6' N.50° E. 1.43'

PEER GROUP APPROVED
Richard L. Drahn 6/9/99
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date May 23, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 29, 1971
REVISED MAY 14, 1976

USFS A-23

REVISED JAN., 1983
REVISED OCT., 1986