

**SURVEY & REMONUMENTATION**

AUG 08 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County }

Received for record the  
11<sup>th</sup> day of JUNE  
A. D. 1997 at 10:45 o'clock  
4 m., and recorded in  
Lib. 6 of CORNERS  
# 145  
Colleen M. Kieker, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic

Located In:

Corner Code #

(County)

1. Public Land Survey

<u>T47NR</u>	<u>44W</u>	<u>A-4</u>
<u>T47NR</u>	<u>45W</u>	<u>M-4</u>
T	R	
T	R	

2. Property Controlling in Section

S	T	R	
S	T	R	

3. Miscellaneous Property in Sec.

S	T	R	
S	T	R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1/4 cor. comm. to sec's 7 & 12

I, John P. Goss, in a field survey on June 2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on Sept. 1, 1847. Set Sugar post.  
Original bearing trees: Sugar 22" S 24° E 23 links  
Elm 16" S 74 1/2° W 25 links

On July 7, 1986, Richard Drahn RLS, restored corner position at record bearing and distance from stump holes of the two original bearing trees. Corner position verified by retracement measurement North and South from corner to recovered natural feature ties. He set a 2" I.D. iron pipe with 3" Circular brass cap, stamped to indicated the corner position. He established the following reference objects: 15" S. Maple - N 04° E - 15.35'; 7" S. Maple - S 18° E - 36.90';

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6" S. Maple - S 76° W - 27.40'; 6' Metal Sign Post - N 31° E - 2.8'.

No original evidence could be found.

Found R. Drahn 2" I.D. iron pipe with 3" circular brass cap. It checked with R. Drahn witnesses. I updated the accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED

Richard Drahn 6/10/97  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2" I.D. iron pipe with 3" brass comp marked: T.47 N., R.44-45 W.; S-7, S-12; 1/4; 1986; R.L.S. 21564. I established the existing and new bearing trees and reference objects.

18" Sugar Maple	N 04° E	15.35'
10" Sugar Maple	S 18° E	36.90'
8" Sugar Maple	S 76° W	27.40'
6' Metal Sign Post	N 31° E	2.8' (to face of post)
6' Rail & Sign	N 70° W	2.5' (to face of post)

(measurement to nail in side of tree)



Signed by John P. Goss  
Surveyor's Michigan License No. 23509

Date June 4, 1997

Fed. No. G-25