

**SURVEY &  
REMONUMENTATION**

AUG 08 1997

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in

Gogebic  
(County)

Located In:

Corner Code #

1. Public Land Survey

T47NR 44W A-11  
T47NR 45W M-11

T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_

2. Property Controlling  
in Section

S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

Received for record the  
13<sup>TH</sup> day of MAY  
A. D. 1997 at 2:10 o'clock  
P M., and recorded in  
Liber 6 of CORNERS  
on page 123  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Sec. cor, comm. to sec's. 25, 36, 30 & 31

I, John P. Goss, in a field survey on May 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt in 1847. Set Ironwood post.  
Original bearing trees: Hemlock 18"-S16°W-16 links; Hemlock 12"-N 49°30'E-38links;  
Hemlock 12"-N50°E-35 links; Lynn 16"-S55°E-40 links.  
Donald Lappala, RLS, set a 3/4" iron pin in centerline of road and record distance 1/2 mile north and south from recovered quarter corners in accordance with GLO field notes. He record this corner in Forest Service Records in Register of Deeds Office for Gogebic County. He established the following corner accessories: 10" S. Maple- N 24° E- 78.3'; 7" S. Maple- S 57° E- 35.9'; P.Pole #36-93/93- S 45° W- 49.6'; reference monument, stamped to indicated corner position-

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

R.M. - West- 52.56'  
On May 18, 1989 Richard Drahn, RLS, replaced destroyed iron pin with a 1.5 ft. gal'v. iron pipe with 3" bronze table stamped: T47N, R44-45W; S-25, S-36, S-30 & S-31; 1989, RLS. 12564 at corner position.  
No original evidence found due to road construction.  
I found Drahn monument and it check with Lappala witnesses. I updated the accessories as noted below to state and county specification.

Act 74 research on file.

R. Drahn recorded his corner in Liber 3 page 308 of Land Corners for Gogebic County

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the Monument set by R. Drahn, I established the existing and new bearing trees and reference objects.

15" Sugar Maple N 24° E 78.34'  
12" Sugar Maple S 57° E 35.94'  
11" Sugar Maple S 21° W 62.85'

Reference Monument consisting of 2 1/2" iron pipe with 3" bronze table which read: T.47 N; R.44-45 W.; R.M.; S-25, S-36, S-30, S31; East 52.56 feet; R.L.S. 12585; 1970

(All measurements taken to a nail in side of tree)

Signed by John P Goss

Date May 5, 1997

Surveyor's Michigan License No. 23509

Fed. No. V-25

PEER GROUP APPROVED

Richard P. Drahn 5/12/97  
COUNTY REPRESENTATIVE

