

SURVEY & REMONUMENTATION

NOV 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
18TH day of AUGUST
A. D. 1997 at 11:00 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 180
Ramona Collins, Deputy
Register of Deeds

For corners in

Gogebic
(County)

Located In: Corner Code #

1. Public Land Survey T 47N R 44W B-1
T R
T R
T 48N R 44W B-13
T R
T R

2. Property Controlling in Section S T R
S T R

3. Miscellaneous Property in Sec. S T R
S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

$\frac{1}{4}$ Cor. 6 & 31; T.47-48 N., R.44 W.

I, Richard L. Drahn in a field survey on August 5, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on August 11, 1847. Original B.T.s --- Fir 10" N.31 E. 11 links (7.26') --- Fir 8" N.21 W. 24 links (15.84') ---

Corner re-established by R. Drahn (21564) by single proportionate methods on 10/29/86. He set a 3/4" X 4' aluminum marsh rod with a 3 1/2" stamped alum. cap and the following new B.T.s: 8" (10") Cedar N.06 W. (N.05 W.) 5.17' (5.15') --- 10" (11") Black Spruce N.87 E. (N.87 E.) 12.85' (12.80') --- 6" (8") Cedar S.47 W. (S.49 W.) 13.15' (13.14') --- 6' Steel sign post S.11 E. (S.08 W.) 2.1' (2.05') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County in Liber 3, Page 27 on 3/4/87.

Recovered the corner as described and the bearing objects as indicated in parentheses above. No evidence remains of the original B.T.s.

Research form on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument I established the following new B.T.:

5" Cedar S.23 E. 6.18'

PEER GROUP APPROVED
Richard L. Drahn 8/13/97
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date August 8, 1997

Surveyor's Michigan License No. 21564