

SURVEY & REMONUMENTATION

OCT 03 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
10TH day of JUNE
A. D. 1996 at 10:00 o'clock
10 m., and recorded in
Liber 5 of CORNERS
on page 365.
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N.</u> R <u>44W.</u>	<u>B-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner 18 & 19; T.47 N., R.44 W.

I, Richard L. Drahn in a field survey on May 21, 19 96 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7	●												
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Corner established by William Burt in 1848. Original B.T.s --- Sugar 10" N.05 E. 15 links (9.90') --- Fir 10" S.65 W. 15 links (9.90'). --- Corner restored by Richard L. Drahn, RLS 21564 on 5/2/83 by single proportionate methods. He set a 30" aluminum monument with a 3 1/4" stamped aluminum cap and the following new bearing objects: --- 10" (12") Sugar Maple N.54 W (N.51 W.) 14.33' (14.33') --- 8" Sugar Maple (10") N.39 E. (N.44 E.) 29.84' slope distance (29.84' slope) --- 14" (14") Hemlock (dead) S.32 W. (S.35 W. 48.71' (48.70') --- 6' Steel sign rail N.02 E (N.05 E.) 1.64' (1.65').

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Corner recorded in Gogebic County in Liber 2, Page 569 on 2/15/84.

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing objects as noted in parentheses above. No evidence remains of the original B.T.s.

PEER GROUP APPROVED
Richard L. Drahn 5/2/96
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Bearing tree referenced:

11" Sugar Maple S.26 E. 18.20'



Signed by Richard L. Drahn Date May 29, 1996

Surveyor's Michigan License No. 21564