

SURVEY & REMONUMENTATION

NOV 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in
Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>47</u> NR <u>44</u> W	<u>B-9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Received for record the
19TH day of SEPT
A. D. 1997 at 10:45 o'clock
A m., and recorded in
Liber 6 of CORNERS

on page 193
Rasmere Colium Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John P. Goss, in a field survey on Sept. 17 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 cor. comm. to sec's. 19 & 30

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Burt in 1848.

Original bearing trees: Cedar 18" N 45° W 8 links
Cedar 12" S 43° E 18 links

On September 28, 1970, Donald D. Lappala, RLS, restored corner position at record bearing and distance from the two original bearing trees. The first one a large cedar windfall. The second one is a 14" to 16" decay cedar windfall with scribing visible in the G.L.O. Blaze. He set a 2 1/2" iron pipe with 3" bronze cap stamped to indicated the corner position. No bearing trees established; No trees within 300 to 400 feet of corner. Someone added a 4"x4" wood post - S 19° E - 1.55'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in USFS Liber R-3, on August 10, 1972.

Found Donald D. Lappala Corner monument and witness.

I updated the Corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2 1/2" iron pipe with 3" bronze cap which read: T.47 N., R.44 W.; 1/4; S-19, S-30; R.L.S. 12585; 1970. I established bearing tree and reference objects.

3" Tagelder	S 40° W	26.45'
4"x4" wood Post & sign	S 19° E	1.51' (to face)
6' Rail & sign	N 62° E	3.15' (to face)
6' Rail & Sign	N 54° W	2.87' (to face)

(measurement to nail in side of tree)

PEER GROUP APPROVED

Richard D. Deahn 9/17/97

COUNTY REPRESENTATIVE

Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date September 17, 1997



Fed. No. R-3