

**SURVEY &
REMONUMENTATION**

NOV 12 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>47N</u> R <u>44W</u>	<u>C-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sec. Cor. 5, 6, 7 & 8; T.47 N., R.44 W.

I, Richard L. Drahn in a field survey on August 6, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s --- Elm 8" N.10 E. 42 links (27.72') --- Sugar 20" S.35 W. 5 links (3.30') ---

Corner restored on 8/3/83 by R. Drahn (21564) from the remains of the two original B.T.s, line trees north and west and distance to recovered corners north and east. He set a 2' X 30" alum. pipe with a 3 1/4" stamped alum. cap and the following new B.T.s: --- 13" (16") White Ash N.57 W. (N.57 W.) 49.43' (49.44') --- 10" (12") Yellow Birch N.82 E. (N.82 E.) 55.72' (55.72') --- 13" (15") Sugar Maple S.27 W. (S.28 W.) 28.05' (28.01') --- 6' Steel sign rail N.06 W. (N.04 W. 2.43' (2.46')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County in Liber 2, Page 555 on 1/26/84.

Recovered the corner as described and the bearing objects as indicated in parentheses above. Stump holes are all that remain of the original B.T.s.

Research form on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument I established the following new B.T.:

5" Sugar Maple s.31 E. 21.98'

PEER GROUP APPROVED

Richard L. Drahn 8/13/97
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date August 8, 1997

Surveyor's Michigan License No. 21564

USFS E-5

Register's Office }
Gogebic County } SS.

Received for record the
18th day of AUGUST
A. D. 1997 at 11:00 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 183;
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

