

**SURVEY &  
REMONUMENTATION**

OCT 03 1996

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>44W.</u>	<u>C-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 19 & 20; T.47 N., R.44 W.

I, Richard L. Drahn in a field survey on May 13, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by William Burt in 1848. Original B.T.s --- Maple 6" N.45 E. 8 links (5.28') --- Hemlock 12" S.50 W. 30 links (19.80') ---  
Corner restored by Donald D. Lappala, RLS 12585, on 9/28/70 by retracement measurement to recovered natural feature ties and line trees. He set a 2½" by 5' iron pipe with a 3" stamped brass cap and the following new bearing trees: --- Sugar Maple 7" (dead) N.51 E. 113.9' --- Red Maple 7" (8") N.89 E. (N.85 E.) 115.1' (115.12') --- Sugar Maple 9" (13") S.12 W. (S.13 W.) 69.2' (68.88' slope distance) ---  
Corner recorded in Gogebic County in USFS Liber, Page P-5 on 8/10/72.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing objects as noted in parentheses above. No evidence remains of the original bearing trees. Corner location falls in pipeline clearing.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Bearing objects referenced:

- 8" Black Ash N.65 E. 95.06'
- 6' Steel sign rail N.37 W. 1.4'

Register's Office } ss.  
Gogebic County }

Received for record the  
10<sup>th</sup> day of JUNE  
A. D. 1996 at 10:00 o'clock  
A m., and recorded in  
Liber 5 of CORNERS  
on page 367  
Bonora Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**PEER GROUP APPROVED**  
Richard L. Drahn 6/6/96  
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date May 13, 1996  
Surveyor's Michigan License No. 21564