

SURVEY & REMONUMENTATION

NOV 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
18TH day of SEPTEMBER
A. D. 1997 at 10:45 o'clock
A m., and recorded in
Liber 6 of COLLINGS
on page 198
Kamera Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey

T47NR L44W C-11

T ___ R ___

T ___ R ___

T ___ R ___

S ___ T ___ R ___

S ___ T ___ R ___

S ___ T ___ R ___

S ___ T ___ R ___

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, John P. Goss, in a field survey on AUG. 21 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Sec. cor. comm. to sec's. 29, 30, 31 & 32

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Burt, in 1848.

Original bearing trees: Spruce 7" N 65° E 34 links
Spruce 14" S 60° W 106 links

On September 23, 1970, Donald Lappala, RLS, found corner position marked by 3" x 36" angle iron at recorded bearing and distance from the decayed stumps of the two spruce bearing trees. Corner position verified further by measurement to recoverable natural features. He set a 2 1/2" iron pipe with 3" bronze cap, marked to indicated corner position. He established the following bearing trees: 8" Spruce- N 55° W- 50.1 links; 10" Spruce-N 10° W- 41.2 links. No other trees in area.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In 1992 John Garske added the following.
12" Spruce- S 82° W - 80.61'; 4"x4" Wood post- S 18° W- 2.5'
Corner recorded in USFS Liber V-5 on August 10, 1972.
Recovered the monument and witnesses items from above.

I updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From the 2 1/2" iron pipe with 3" bronze cap which reads: T.47 N., R.44 W.; S-29, S-30, S-31 & S-32; R.L.S. 12585, 1970, from which I established existing bearing trees and exiting and new reference objects:

- 8" Spruce N. 55° W. 49.85'
- 9" Spruce N. 10° W. 41.08'
- 12" Spruce (dead) S. 82° W. 80.61'
- 4" x 4" Wood post & sign. S. 18° W. 1.85' (to face)
- 6' Rail & sign Due North . 1.54'

(measurement to nail in side of tree)
Signed by John P. Goss
Surveyor's Michigan License No. 23509

PEER GROUP APPROVED
Richard P. Deahn 9/17/97
COUNTY REPRESENTATIVE

Date August 21, 1997



Fed. No. V-5