

NOV 1 2 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
18<sup>TH</sup> day of SEPTEMBER  
A. D. 1997 at 10:45 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
page 199  
Ramona Collins Deputy  
Register of Deeds

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47</u> N R <u>44</u> W	<u>C-12</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, John P. Goss, in a field survey on Aug. 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 cor. comm. to sec's. 31 & 32

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Burt in 1848.  
Original bearing trees: Maple 4" S 15° E 37 links  
Maple 12" N 20° W 50 links

On October 2, 1970, Donald D. Lappala, RLS, restored corner position at record bearing and distance from the stump holes of the two original bearing trees. corner position verified further by retracement measurement of the section line south from corner to recoverable record natural features. He set a 2 1/2" iron pipe with 3" bronze cap which indicated the corner position. He established the following bearing trees: 6" S. Maple - N 44° W - 21.9'; 7" S. Maple - N 10° E -

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

40.6'; 6" S. Maple - S 53° E - 5.1'.  
Corner recorded in USFS Liber X-5, on August 10, 1972.  
Found Donald D. Lappala, monument and witnesses.

I updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2 1/2" iron pipe with 3" bronze cap which reads: T.47 N., R.44 W.; 1/4; S-31, S-32; R.L.S. 12585; 1970, from which I established existing and new bearing trees and reference object.

- 9" Sugar Maple N 44° W 21.87'
- 10" Sugar Maple N 10° E 40.62'
- 7" Sugar Maple S 53° E 5.25'
- 6" Sugar Maple Due W 26.70'
- 6' Rail & Sign Due S 1.38 (to face)

(All measurement to nail in side of tree)

Signed by John P. Goss  
Surveyor's Michigan License No. 23509

Date August 29, 1997

Fed. No. X-5

PEER GROUP APPROVED  
Richard L. Drahm 9/17/97  
COUNTY REPRESENTATIVE

