

**SURVEY &
REMONUMENTATION**

NOV 12 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
18th day of AUGUST
A. D. 1997 at 11:00 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 186
Ramona Collins Deaity
Register of Deeds

For corners in

<u>Gogebic</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>44W</u>	<u>D-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Cor. 5 & 8; T.47 N., R.44 W.

Richard L. Drahn, in a field survey on August 7, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3		●										
4	7	8	8	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s --- Sugar 14" N.35 W. 22 links (14.52') --- Hemlock 12" S.30 E. 32 links (21.12')

Corner restored on 8/3/83 by R. Drahn (21564) from the remains of the two original B.T.s, and distances to recovered corners east and west. He set a 2" X 30" aluminum pipe with a 3 $\frac{1}{4}$ " stamped alum. cap and the following new B.T.s: --- 17" (19") Sugar Maple N.19 E. (N.18 E.) 33.24' (33.27')--- 8" (9") Yellow Birch S.31 E. (S.33 E.) 35.02 (35.00')--- 19" (21") Hemlock S.66 W. (S.64 W.) 54.13' (54.36'). ---

Corner recorded in Gogebic County in Liber 2, Page 519 on 1/26/84.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Research form on file with Gogebic County records.

Recovered the corner as described and the bearing objects as indicated in parentheses above. The original Sugar B.T. is now a large, badly decayed stump; and the Hemlock is now a large stump hole.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument I established the following new B.T.s:

- | | | | |
|----|-----------------|---------|--------|
| 6' | Steel sign rail | North | 2.58' |
| 5" | Sugar Maple | N.53 W. | 18.88' |

PEER GROUP APPROVED
Richard L. Drahn 8/13/97
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date August 8, 1997

Surveyor's Michigan License No. 21564