

**SURVEY & REMONUMENTATION**

NOV 12 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic  
(County)

Located In:

Corner Code #

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>47N</u> R <u>44W</u> | <u>D-5</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

Register's Office }  
Gogebic County } ss.

Received for record the  
18<sup>TH</sup> day of SEPTEMBER  
A. D. 1997 at 10:45 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
on page 201  
Lamona Blums, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner S & 17; T.47 N., R.44 W.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	10	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Richard L. Drahn in a field survey on September 13, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by William Burt in 1848. Original B.T.s --- Cedar 10" N.30 W. 18 links (11.88') --- Y. Birch 16" S.25 E. 17 links (11.22') ---

Corner re-established by Richard L. Drahn (21564) by single proportionate methods on 7/22/86. He set a 2" X 36" iron pipe with a 3" stamped brass cap and the following new B.T.s: --- 7" (9") Red Maple N.02 W (N.03 W.) 14.14' (14.06') --- 11" (13") Yellow Birch S.11 E. (S.12 E.) 19.92' (19.84') --- 13" (15") Black Ash S.65 W. (S.65 W.) 39.46' (39.44') --- 6' Steel sign post S.29 E. (N.25 W.) 1.4' (1.32') ---

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Corner recorded in Gogebic County in Liber 3, Page 30 on 3/4/87.

Recovered the corner as described and the bearing objects as indicated in parentheses above. No evidence remains of the original B.T.s.

Research form on file with Gogebic County records.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

From the above described monument I established the following new B.T.:

5" Black Ash S.82 E. 13.16'

PEER GROUP APPROVED

Richard L. Drahn 9/17/97  
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn

Date September 15, 1997

Surveyor's Michigan License No. 21564