

SURVEY & REMONUMENTATION

OCT 03 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 47 NR 44 W.	D-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office } ss.
Gogebic County }

Received for record the
10th day of JUNE
A. D. 1996 at 10:01 o'clock
A m., and recorded in
Liber 5 of CORNERS
on page 369
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner 17 & 20; T.47 N., R.44 W.

I, Richard L. Drahn in a field survey on May 14, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s --- Sugar Maple 12" S.65 E. 20 links (13.20') --- Hemlock 8" N.45W. 20 links (13.20').

Corner restored by Donald D. Lappala, RLS 12585 on 10/16/70 from the remains of the two original bearing trees and a line tree. He set a 2 $\frac{1}{2}$ " by 5' iron pipe with a 3" stamped brass cap and the following new bearing trees: --- Sugar Maple 8" (9") N.09W. (N.05 W.) 13.3' (13.32') --- Yellow Birch 10" (dead stub) S.32 E. 17.7' --- Sugar Maple 7" (8") S.44 W. (S.45 W.) 17.5' (17.43'). ---

Corner recorded in Gogebic County in USFS Liber, Page N-7 on 8/10/72.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Ace 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing objects as noted in parentheses above.

A stump hole remains from the original Sugar B.T. and fragments of hemlock bark from the original Hemlock B.T.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7		●										
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

PEER GROUP APPROVED
Richard L. Drahn 6/6/96
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing objects referenced:

- 4 X 4 X 7' Cedar sign post S.30 E. 2.25'
- 6' Steel sign rail N.55 W. 3.45'
- 7" Sugar Maple S.63 E. 24.57'



Signed by Richard L. Drahn

Date May 20, 1996

Surveyor's Michigan License No. 21564