

NOV 12 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
18TH day of SEPTEMBER
A. D. 1997 at 10:45 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 202
Ramona Collins Deputy
Register of Deeds

For corners in

Gogebic (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47</u> N R <u>44</u> W	<u>D-11</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John P. Goss, in a field survey on Sept. 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 cor. comm. to sec's 29 & 32, T47N, R44W

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Burt in 1848. Set post.
Original bearing trees: Fir 12" N 80° W 8 links
Fir 6" S 30° E 10 links

John R. Garske re-established corner by single proportional measurements on Jan. 29, 1992. He set a 2½" by 30" aluminum pipe with 3" aluminum tablet stamped to indicated corner position. He recorded said corner in Liber 4 page 69 of Land corners for Gogebic County with the following witnesses: Wood Post- Due S- 14.75'; 8" Balsam- S 16° W-7.81'; 12" Cedar- N 50° W- 22.16'; 12" Balsam- S 43° E 12.79'; Steel rail & sign - Due North - 2.50'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found.
Found J.R. Garske 2½" Aluminum pipe with 3" aluminum cap. It checked with his witnesses. I updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2½" by 30" aluminum pipe with 3" aluminum tablet stamped to read: 1/4 cor.; S-29, S-32; T47N, R44W; 1992; RLS 28410. Following are bearing trees and/or reference objects.

Wood Post	Due South	14.75'
9" balsam	S 16° W	7.81'
12" cedar	N 50° W	22.62'
10" balsam	S 43° E	12.79'
Steel rail & sign	Due North	2.65'
15" balsam	N 37° E	9.15'

(measurement to nail in side of tree)
Signed by John P. Goss

Surveyor's Michigan License No. 23509

Fed. No. V-7

PEER GROUP APPROVED

Richard P. Dealm 9/17/97
COUNTY REPRESENTATIVE



Date Sept. 1, 1997