

NOV 12 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in

Gogebic  
(County)

Located In: Corner Code #

- 1. Public Land Survey T46NR 44W D-1  
T47NR 44W D-13
- 2. Property Controlling In Section S \_\_\_ T \_\_\_ R \_\_\_
- 3. Miscellaneous Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_

Received for record the  
18<sup>th</sup> day of SEPTEMBER  
A. D. 1997 at 10:45 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
on page 203  
Remona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, John P. Goss, in a field survey on Aug. 18, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1			●									
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13			●									

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 cor. comm. to sec's. 5 & 32

A. Description of original monument and accessories and/or subsequent restoration:  
Original corner established by Austin Burt in 1847.  
Original bearing trees: Spruce N 37° W 41 links  
White Pine N 76° E 37 links  
On October 5, 1970, Donald D. Lappala, RLS, restored corner position at record bearing and distance from the two original bearing trees: A large decayed spruce stump and a 30" decayed white pine stump with scribed visible. He set a 2½" iron pipe with 3" cap and new B.T. - 12" Black Spruce N 33° W- 23.0'; 9" Cherry- N 13° E - 38.2'; 4" White Spruce- S 26° W- 10.3'. Corner recorded in USFS Liber Z-7, on August 10, 1972.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
In 1992 a 4" by 4" wood post North and a 3" Maple- N 59° W- 22.96' was added.  
Recovered the monument as described above and 2 bearing trees and 1 stump. Also recovered a large spruce stump from original bearing trees;

I updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED  
Richard P. Deahn 9/17/97  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
From the 2½" iron pipe with 3" bronze cap which reads: T. 46-47 N., R.44 W.; 1/4; S-5, S-32; R.L.S. 12585; 1970; from which I established the existing and new bearing trees and reference objects:

- 12" Black Spruce (stump) N 33° W 23.0'
  - 12" Cherry N 13° E 38.23'
  - 9" White Spruce S 26° W 10.35'
  - 4" Maple N 59° W 22.90'
  - 4"x4" wood post & sign N 30° W 1.15' (to face)
  - 6' Rail and sign Due S. 1.57' (to face)
- (measurement to nail in side of tree)



Signed by John P. Goss  
Surveyor's Michigan License No. 23509

Date August 18, 1997

Fed. No. Z-7