

NOV 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

Received for record the
18th day of AUGUST
A. D. 1997 at 11:00 o'clock
A m., and recorded in
Lib. 6 of CORNERS
page 185

Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 47N R 44W E-3
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Sec. Cor. 4, 5, 8 & 9; T.47 N., R.44 W.

Richard L. Drahn in a field survey on August 11, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s --- Hemlock 12" N.55 E. 15 links (9.90') --- Hemlock 24" S.40 W. 44 links (29.04') ---

Corner restored by R. L. Drahn (21564) on 8/3/83 from the remains of the two original B.T.s. He set a 2" X 30" aluminum pipe with a 3 1/4" stamped alum. cap and the following new B.T.s: --- 5" (8") Hemlock N.40 W. (N.40 W.) 9.54' (9.52') --- 5" (7") Sugar Maple N.72 E. (N.74 E.) 35.38' (35.39') --- 10" Sugar Maple (now dead and down) S.24 W. 33.23' --- 6' Steel sign rail N.60 W. (N.61 W.) 1.94' (1.91') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County Liber 2, Page 571 on 2/15/84.

Corner research on file with Gogebic County records.


Recovered the monument as described and the bearing trees as noted in parentheses above. A windthrown stump hole remains from the original Hemlock at N.55 E. and a very large Hemlock stump, decayed to below ground line bears S.40 W. 29.0'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument I established the following new B.T.:

7" Sugar Maple S.43 W. 43.14'

PEER GROUP APPROVED
Richard L. Drahn 8/13/97
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date August 11, 1997

Surveyor's Michigan License No. 21564