

Register's Office }  
Gogebic County } ss.

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Received for record the  
10<sup>th</sup> day of JUNE  
A. D. 19 96 at 10:00 o'clock  
A. m. and recorded in  
Liber 5 of CORNERS

on page 372  
Ramona Collins, Deputy  
Registrar of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic  
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 47N R 44 W. E-8  
T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

1/4 Corner 20 & 21; T.47 N., R.44 W.

Richard L. Drahn in a field survey on May 14, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s --- Y. Birch 15" N.60 E. 12 links (7.92') --- Sugar 5" West 12 links (7.92').

Corner restored by Donald D. Lappala, RLS 12585 on 9/22/70 from the remains of the original bearing trees and a natural feature tie. He set a 2 1/2" by 5" iron pipe with a 3" stamped brass cap and the following new bearing trees: --- Elm 5" (dead and down) N.49 W. 27.0' --- 5" Sugar Maple (dead and down) S.59 E. 17.0' --- 9" Elm (dead and down) S.06 W. 14.9'.

Corner recorded in Gogebic County in USFS Liber, Page P-9 on 8/10/72.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing objects as noted in parentheses above. No evidence remains of the original bearing trees.

BEER GROUP APPROVED

Richard L. Drahn 6/6/96  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing objects referenced:

- 10" Hemlock S.42 W. 38.19'
- 12" Red Maple N.41 W. 11.33'
- 6" Sugar Maple N.89 E. 35.49'
- 4 X 4 Cedar sign post S.68W. 2.2'
- 6' Steel sign rail S.74E. 1.75'



Signed by Richard L. Drahn

Date May 20, 1996

Surveyor's Michigan License No. 21564