

**SURVEY & REMONUMENTATION**

OCT 0 8 1985

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

For corners in

Gogebic  
 (County)

Located In:

Corner Code #

- |                                    |                             |            |
|------------------------------------|-----------------------------|------------|
| 1. Public Land Survey              | T <u>47N</u> R <u>44</u> W. | <u>E-9</u> |
|                                    | T _____ R _____             | _____      |
|                                    | T _____ R _____             | _____      |
|                                    | T _____ R _____             | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____     | _____      |
|                                    | S _____ T _____ R _____     | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____     | _____      |
|                                    | S _____ T _____ R _____     | _____      |

Received for record the 8<sup>th</sup> day of MAY

A. D. 1996 at 11:00 o'clock

A m., and recorded in Liber 5 of CORNER

on page 346

Karmona Collins, Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Sec. Cor. 20, 21, 28 & 29 T.47 N., R.44 W.

I, Richard L. Drahn in a field survey on May 6, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 Corner established by William Burt in 1848. Original B.T.s --- Sugar Maple 16" S.55 E. 8 links (5.28') --- Sugar Maple 10" N.59 W. 40 links (26.40').  
 Corner restored by Donald D. Iappala, RLS 12585 from the stump holes of the two original bearing trees and from natural feature ties north, south and east. He set a 2½" by 5' iron pipe with a 3" stamped brass cap and the following new bearing tree; --- 5" (8") Elm (live) N.82 W. (N.80 W.) 20.6' (20.58') --- 7" (15") Spruce N.08 W. (N08 W.) 36.5' (36.64') --- 9" (18") Spruce S.80 E. (S.78 E.) 46.4' (46.45').

Corner recorded in Gogebic County in USFS Liber, Page R-9 on 8/10/72.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing objects as noted in parentheses above. Depression is all that remains of the original SE B.T..


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing objects referenced:

4" x 4" Cedar sign post	N.61 W.	1.75'
6' Steel sign rail	S.56 E.	3.1'

PEER GROUP APPROVED

Richard L. Drahn 5/7/96  
 COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date May 7, 1996  
 Surveyor's Michigan License No. 21564