

SURVEY & REMONUMENTATION

OCT 03 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>44W.</u>	<u>E-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office } ss.
Gogebic County }

Received for record the
8TH day of MAY
A. D. 1996 at 11:00 o'clock
A m., and recorded in
Liber 5 of CORNERS
on page 345.

Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner 28 & 29; T.47 N., R.44 W.

I, Richard L. Drahn in a field survey on May 6, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s --- Maple 24" S.43 E. 28 links (18.48') --- Hemlock 8" N.52 W. 7 links (4.62). R.G. Cambell on 3/28/35 recovered the Hemlock B.T. Corner restored by Donald D. Lappala, RLS 12585 on 8/29/68 from the remains of the two original B.T.s. He set a 2" x 5' iron pipe with a 3" brass cap and the following new bearing trees: 5" Elm (dead & down) N.49 E. 46.3' --- 8" Elm N.87 E. 30.0' (dead stub) --- 4" Elm S.55 E. 37.5' (dead stub).

Corner recorded in Gogebic County in USFS Liber, Page T- 9 on 4/14/69.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing objects as noted in parentheses above. No evidence remains of the original B.T.s.

Act 74 research form on file with Gogebic County records.

PEER GROUP APPROVED

Richard L. Drahn 5/7/96
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing objects referenced:

- 4"x 4" Cedar sign post N.64 E. 1.5'
- 6' Steel sign post N.28 E. 2.66'
- Chain link fence post S.09 W. 10.21'
- 7" Black Ash S.79 E. 21.09'



Signed by Richard L. Drahn

Date May 7, 1996

Surveyor's Michigan License No. 21564