

NOV 1 2 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic (County)	Located in:	Corner Code #
1. Public Land Survey	T47NR44W	E-12
	T___R___	_____
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____

Received for record the
18th day of SEPTEMBER
A. D. 1997 at 10:45 o'clock
4 m., and recorded in
Liber 1 of CORNERS
page 206
Bonnie Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John P. Goss, in a field survey on Sept. 2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 cor. comm. to sec's 32 & 33, T47N, R44W

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Burt in 1848.
Original bearing trees: Fir 10" N 25° E 25 links
Maple 18" N 30° W 12 links

On October 23, 1970 Donald D. Lappala, R.L.S., restored corner position at record bearing and distance from the stump holes of the two original bearing trees. He also verified location by retracement measurements to natural features and line trees. He set a 2 1/2" Iron pipe with 3" circular tablet indicated corner position. He record said corner in Forest Service Records in Gogebic Court house under T.47 N., R.44 W.- X-9 : with the following witnesses:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

10" Yellow Birch N 44° W 17.8'
8" Sugar Maple N 49° E 20.4'
9" Sugar Maple S 35° E 6.8'
In 1991 John Garske add the following
6" Sugar Maple N 10° W 39.37'
4'x4' wood post S 45° W 3.1'

PEER GROUP APPROVED
Richard P. Dehn 9/17/97
COUNCIL REPRESENTATIVE

Found Donald D. Lappala 2 1/2" Iron pipe with 3" Circular tablet.
I updated the corner monument and accessories as noted below to state and Act 74 research on file. County specification.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2 1/2" iron pipe with 3" circular tablet which read: T.47 N., R.44 W.; 1/4; S-32, S-33, R.L.S. 12585, 1970. Following are bearing trees and/or reference objects.

10" Yellow Birch N 44° W 17.8' stump only
11" Sugar Maple N 51° E 20.42'
11" Sugar Maple S 35° E 6.58'
7" Sugar Maple N 10° W 39.37'
4'x4' wood post S 45° W 2.9' to face
6' Rail & sign Due North 2.2' to face
(measurement to nail in side of tree)

Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date Sept. 2, 1997

Fed. No. X-9

