

**SURVEY & REMONUMENTATION**

NOV 12 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

Received for record the  
18<sup>TH</sup> day of SEPTEMBER  
 A. D. 1997 at 10:42 o'clock  
A m., and recorded in  
 Liber 6 of CORNERS

on page 207  
Barbara Collins Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>44W</u>	<u>F-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 9 & 16; T.47 N., R.44 W.

Richard L. Drahn, in a field survey on September 12, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s --- Hemlock 36" N.50 E. 7 links (4.62') --- Sugar 14" South 15 links (9.90') ---

Corner restored on 7/25/83 by Richard L. Drahn (21564) from the decayed remains of the two original B.T.s. He set a 2" X 30" aluminum monument with a 3 $\frac{1}{4}$ " stamped aluminum cap and the following new B.T.s: --- 7" (9") Sugar Maple N.29W. (N.25 W.) 18.87' (18.75') --- 19" (21") Hemlock N.39 E. (N.42 E.) 15.32' (15.33') --- 14" (16") Sugar Maple S.13 W. (S.15 W.) 11.36' (11.01') --- 6' steel sign rail N.45 W. (N.37 W. re-set) 1.66' (1.54') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County in Liber 2, Page 579 on 2/15/84.

Recovered the corner as described and the bearing trees as indicated in parentheses above. Stump holes are all that remain of the two original B.T.s.

Research form on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument I established the following new B.T.

6" Sugar Maple S.72 E. 14.02'

PEER GROUP APPROVED  
Richard L. Drahn 9/17/97  
 COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date September 15, 1997

Surveyor's Michigan License No. 21564