

**SURVEY & REQUIRMENTATION**

OCT 03 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Register's Office } ss.  
 Gogebic County }

Received for record the  
10<sup>TH</sup> day of JUNE

A. D. 1996 at 10:00 o'clock

A m., and recorded in  
 Liber 5 of CORNERS

on page 375  
Ramona Collins, Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

Gogebic (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>44W</u> .	<u>F-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 21 & 28; T.47 N., R.44 W.

Richard L. Drahn in a field survey on May 22, 1996  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
 expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
 on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s --- Sugar 8"  
 N.40 E. 7 links (4.62') --- Y. Birch 18" S.10 W. 21 links (13.86').  
 Corner restored by Donald D. Lappala, RLS 12585 from the stump holes of the  
 two original B.T.s and from natural features east and west. He set a 2 $\frac{1}{2}$ "  
 iron pipe with a 3" stamped brass cap and the following new bearing trees:  
 --- 7" (11") Spruce N.71 E. (N.70 E.) 19.7 (19.71') --- 5" (7") Sugar Maple  
 S.27 W. (S.27 W.) 28.3' (28.23') --- 14" (18") Sugar Maple S.61 W. (S.63 W.)  
 31.0' (31.16'). Corner recorded in Gogebic County in USFS Liber, Page R-11.  
 Act 74 research form on file with Gogebic County records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing objects as noted in  
 parentheses above.

No evidence remains of the original bearing trees.

PEER GROUP APPROVED  
Richard L. Drahn 6/6/96  
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing objects referenced:

4" X 4" Cedar sign post S.04 E. 2.25'  
 6' Steel sign rail N.11 E. 1.9'



Signed by Richard L. Drahn

Date May 29, 1996

Surveyor's Michigan License No. 21564