

**SURVEY &  
REMONUMENTATION**

OCT 03 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office } ss.  
Gogebic County }

Received for record the  
10<sup>TH</sup> day of JUNE  
A. D. 1996 at 10:00 o'clock  
A m., and recorded in  
Liber 5 of CORNER  
on page 376.  
Ramona Collins, Deputy  
Register of Deeds

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>44W.</u>	<u>F-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 28 & 33; T.47 N., R.44 W.

I, Richard L. Drahn, in a field survey on May 22, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s --- Ironwood 10" N.67 E. 26 links (17.16') --- Y. Birch 18" S.70 W. 13 links (8.58').

Corner re-established by Richard L. Drahn, RLS 21564 on 4/9/81 by proportionate methods. He set a 30" long aluminum pipe with a 3 $\frac{1}{4}$ " stamped aluminum cap and the following new bearing objects: --- 7" (9") Sugar Maple N.71 W. (N.68 W.) 30.27' (30.31') --- 8" Sugar Maple (11") N.03 W. (N. 03 W.) 34.90' (34.87') --- 6" (7") Sugar Maple S.09 W. (S.12 W.) 10.18' (10.17'). --- 7' Steel sign rail N.02 W. (N.01W.) 2.75' (2.75').

Corner recorded in Gogebic County in Liber 2, Page 246 on 3/10/82.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing objects as noted in parentheses above.

No evidence of the original bearing trees was found.

PEER GROUP APPROVED  
Richard L. Drahn 6/6/96  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

~~XX~~ new bearing objects established.

8" Sugar Maple S.62 W. 8.50'



Signed by Richard L. Drahn

Date May 29, 1996

Surveyor's Michigan License No. 21564