

NOV 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located in:

Corner Code #

1. Public Land Survey

T46NR44W F-1
~~T47NR44W F-13~~

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R
S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register's Office }
Gogebic County } ss.

Received for record the
10TH day of SEPTEMBER

A. D. 1997 at 10:45 o'clock

A m., and recorded in

Liber 6 of CORNERS

SS. page 208

Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

I, John P. GOSS, in a field survey on Aug. 14 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 cor. comm. to sec's. 4 & 33

	A	B	C	D	E	F	G	H	I	J	K	L	M
1						●							
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13						●							

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, in 1847.
Original bearing trees: Hemlock 36" N 22° E 15 links
S. Maple 12" N 41° W 27 links.

On October 20, 1970, Donald D. Lappal, RLS, restored corner position at record bearing and distance from the stump hole of the two original bearing trees. Corner position verified further by measurement to recoverable record natural features and record line tree. He set a 2½" I. pipe with 3" bronze cap and new B.T. - 10" Elm- N12°W- 39.1'; 5" R. Maple- N54°E- 17.5'; 7" Elm- S 72°W- 13.8'. Corner recorded in USFS liber, Z-11 on August 10, 1972.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and 1 bearing tree and stump hole of 10" Elm N 12° W 39.1'.
I updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From the 2½" iron pipe with 3" bronze cap which reads: T. 46-47 N, R.44 W.; 1/4; S-4, S-33; R.L.S. 12585; 1970, from which I established existing and new bearing trees and reference objects:

- 6" Red Maple N 54° E 17.53'
- 7" Maple N 34° W 12.00'
- 6" Tw. Maple S 30° W 27.70'
- 4"x4" wood post & sign N 36° E 3.3' (to face)
- 6' Rail & sign Due S 1.1' (to face)

(Measurement to nail in side of tree)

Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date August 15, 1997

PEER GROUP APPROVED
Richard L. Deane 9/17/97
COUNTY REPRESENTATIVE



Fed. No. Z-11