

NOV 12 1997

Commissioner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office
Gogebic County ss.

Received for record the
18th day of SEPTEMBER
A. D. 1997 at 10:50 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 212
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 47N R 44W G-4
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

1/4 Corner 9 & 10; T.47 N., R.44 W.

Richard L. Drahn, in a field survey on September 14, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column I and row 4.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s: --- W. Birch 8" N.35 W. 16 links (10.56') --- W. Pine 8" S.36 E. 17 links (11.22') ---

Corner restored on 6/24/83 by Richard L. Drahn (21564) by retracement measure to recovered line trees, natural features and recovered corners north and south. The original B.T.s had been destroyed by logging operations. He set a 2" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following new B.T.s: --- 16" (19") Hemlock N.45 E. (N.46 E.) 12.06' (12.28') --- 8" (12") Hemlock S.09 E. (S.10 E.) 38.76' (38.50') --- 8" (9") Red Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

S.88 W. (S.88 W.) 20.50' (20.27') --- 6' Steel sign rail N.05 W. (N.05 W.) 1.75' (1.91') --- new distances are to a new 10p nail in the B.T.s.

Corner recorded in Gogebic County in Liber 2, Page 581 on 2/15/84.

Recovered the corner as described and the bearing objects as indicated in parentheses above. No evidence remains of the original B.T.s.

Research form on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument I established the following new B.T.:

12" Twin Red Maple (right stem) S.85 E. 10.18'

PEER GROUP APPROVED
Richard L. Drahn 9/17/97
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn

Date September 16, 1997

Surveyor's Michigan License No. 21564