

**SURVEY &
REMONUMENTATION**

OCT 03 1986

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>44W</u>	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office }
Gogebic County } ss.

Received for record the
10TH day of JUNE
A. D. 1996 at 10:00 o'clock
A m., and recorded in
Liber 5 of CORNER
on page 379
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sec. Cor. 27, 28, 33 & 34; T.47 N., R.44 W.

I, Richard L. Drahn in a field survey on May 21, 1996, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
Corner established by William Burt in 1848. Original B.T.s --- Sugar 16" N.40 E. 14 links (9.24'). --- Sugar 12" S.51 W. 51 links (33.66').
Corner restored by Donald D. Lappala, R.L.S. 12585 on October 8, 1969 from the remains of the two original bearing trees and from a natural feature tie and a line tree east. He set a 2½" iron pipe with a 3" stamped brass cap and the following new bearing trees: --- 12" (18") White Spruce N.65 W. (N.64 W.) 65.9' (65.55') --- 14" (19") White Spruce N.77 E. 47.7' (47.23') --- 10" (19") White Spruce S.14 E. (S.13 E) 31.0' (31.32'). ---
Corner recorded in Gogebic County in USFS Liber, Page V-13 on May 27, 1970. Act 74 research form on file with Gogebic County records.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Recovered the monument as described and the bearing objects as noted in parentheses above. No evidence remains of the original bearing trees.

PEER GROUP APPROVED

Richard L. Drahn 6/6/96
COUNTY REPRESENTATIVE

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Bearing objects referenced:

4" X 4" Cerar sign post N.37 W. 2.85'
6' Steel sign rail N.42 E. 1.85'



Signed by Richard L. Drahn Date May 28, 1996
Surveyor's Michigan License No. 21564