

**SURVEY &
REMONUMENTATION**

SEP 08 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }
Gogebic County } ss.

For corners in

Gogebic Located in: Corner Code #
(County)

1. Public Land Survey T47NR 43W H-11
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

Received for record the
23rd day of JULY
A. D. 1998 at 11:35 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 21
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner common to Sec's. 27 & 34, T47N, R44W

I, John P. Goss, in a field survey on June 25th 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848.
Original bearing trees: Y. Birch 12" N 71° E 60 links
Fir 10" S 47° W 35 links

On February 23, 1992, John R. Garske, R.L.S., reestablished corner position by single proportional measurement on line and midway between section corners. He set a 2½" aluminum pipe monument with ¾" aluminum cap stamped to read: T.47 N., R.44 W.: 1/4; S-27, S-34; 1992; RLS 28410. He established the following reference objects. 6" Balsam fir - N 29° E - 113.74'; 10" Balsam fir - S 24° W - 52.21'; 8" Sugar Maple - S 80° W - 44.58'; 6' steel rail & sign - Due South - 2.37' (out)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in Liber 4, page 71 of Land Corners for Gogebic County. No original evidence was found.

Found John R. Garske, monument and three (3) witness trees.

I updated the monument and accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED
Richard L. Dralun 7/22/98
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument, I established the following existing and new reference objects:

8" Balsam Fir N 29° E 113.74'
12" Balsam Fir S 24° E 52.21'
12" Sugar Maple S 80° W 44.58'
6" Ash N 21° W 69.55'

(All measurement taken to nail in side of tree)

Corner is 25.5 feet, more or less, South of southerly gas pipeline center line: Per John R. Garske.



Signed by John P. Goss

Date June 25, 1998

Surveyor's Michigan License No. 23509

U.S.F.S. No. V-15