

SEP 08 1998

Register's Office }
Gogebic County } ss.

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Received for record the
14TH day of MAY

A. D. 1998 at 3:20 o'clock
P. m., and recorded in

Liber 6 of Conveys
on page 361

Ramona Collins, Deputy
Register of Deeds

For corners in

Gogebic
(County)

Located in: Corner Code #

- 1. Public Land Survey T 47N R 44W I-1
T R
T R
T 48N R 44W I-13
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section Corner 2, 3, 34 & 35; T.47-48 N., R.44 W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard L. Drahn in a field survey on April 30, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/11/1847. Original B.T.s --- Sugar 10" N.61 E. 26 links (17.16') --- Sugar 8" N.34 W. 53 links (34.98') --- Sugar 10" S.50 E. 15 links (9.90') --- Y. Birch 14" S.10 W. 20 links (13.20')

Corner restored by Donald D. Lappala (12585) on 8/15/68 from the decayed remains of the four original B.T.s. He set a 2" X 60" iron pipe with a 3" stamped brass cap and the following new bearing trees:

- 5" Sugar Maple S.72 W. 12.6'
- 8" Sugar Maple N.57 E. 21.2'
- 12" Sugar Maple S.16 W. 26.6'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County in USFS Liber, Page Z-17 on 3/31/69.

Corner research on file with Gogebic County records.

Recovered the monument as described and the new bearing trees as follows:

- 7" Sugar Maple S.70 W. 12.67' (new nail)
- 11" Sugar Maple N.61 E. 21.12' " "
- 15" Sugar Maple S.18 W. 26.73' " "

Remains of the original B.T.s are still evident. The original Y. Birch is now a downed, 27" Y. Birch with GLO blazes.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

- 6' Steel sign rail N.13 W. 3.03'
- 4" X 4" x 7' Cedar sign post bears S.40 E. 2.32'



REER GROUP APPROVED
Richard L. Drahn 5/13/98
COUNTY REPRESENTATIVE

Signed by Richard L. Drahn

Date May 3, 1998

Surveyor's Michigan License No. 21564