

**SURVEY &
REMONUMENTATION**

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>44W</u>	<u>T-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office }
Gogebic County } ss.

Received for record the
14th day of MAY
A. D. 1998 at 3:20 o'clock
P m., and recorded in
Liber 6 of CORNERS
on page 362
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner 2 & 3; T.47 N., R.44 W.

I, Richard L. Drahn, in a field survey on April 30, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s --- Sugar 10" N.05 E. 20 links (13.20') --- Fir 8" S.08 W. 20 links (13.20') ---

Corner position re-established by Richard L. Drahn (21564) on 12/4/90 by single proportionate methods. He set a 3/4" X 4' solid aluminum rod with a 3 1/4" stamped aluminum rod and the following new B.T.s:

- | | | | |
|----|-----------------|---------|--------|
| 8" | Sugar Maple | N.20 W. | 9.89' |
| 7" | Sugar Maple | S.76 E. | 7.59' |
| 7" | Black Ash | S.35 W. | 12.00' |
| 6' | Steel sign rail | N.85 E. | 2.15' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County Liber 3, Page 414 on 2/14/91.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

- | | | | |
|----|-----------------|---------|--------|
| 8" | Sugar Maple | N.21 W. | 9.88' |
| 7" | Sugar Maple | S.78 E. | 7.57' |
| 9" | Black Ash | S.35 W. | 11.97' |
| 6' | Steel sign rail | N.84 E. | 2.24' |

No evidence remains of the original corner or bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

- | | | | |
|----|-----------|---------|--------|
| 6" | Red Maple | N.84 W. | 18.72' |
|----|-----------|---------|--------|

PEER GROUP APPROVED
Richard L. Drahn 5/13/98
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date May 3, 1998

Surveyor's Michigan License No. 21564