

**SURVEY & REMONUMENTATION**

SEP 08 1998

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

For corners in SECTION  
Gogebic  
 (County)

Located In: Corner Code #

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>47N</u> R <u>44W</u> | <u>I-4</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

Received for record the  
14<sup>th</sup> day of MAY  
 A. D. 1998 at 3:20 o'clock  
P m., and recorded in  
 Liber 6 of CORNERS  
 on page 364

*Ramona Collins Deputy*  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 10 & 11; T.47 N., R.44 W.

I, Richard L. Drahn in a field survey on April 24, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s --- Cedar 14" West 8 links (5.28') --- B. Ash 10" N.20 E. 30 links (19.80') --- J. J. Maredith recovered the Cedar B.T. on 5/9/35 and placed a location poster on a 6" elm, 10' south of the corner. Donald D. Lappala (12585) on 6/25/74, restored the corner from the remains of the two original B.T.s and Marediths' bearing tree. He set a 2" X 60" iron pipe with a 3" stamped brass cap and the following new B.T.s:

- |     |       |         |       |
|-----|-------|---------|-------|
| 14" | Cedar | N.40 W. | 18.0' |
| 4"  | Cedar | N.63 E. | 27.4' |
| 11" | Cedar | S.10 W. | 52.8' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County USFS Liber, Page G-17 on 3/4/75.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows.

- |     |       |         |                   |
|-----|-------|---------|-------------------|
| 14" | Cedar | N.42 W. | dead and down     |
| 7"  | Cedar | N.65 E. | 27.39' (new nail) |
| 13" | Cedar | S.11 W. | 52.68' " "        |

Portions of a Cedar stump still remains from the first original B.T. and a large shallow depression remains from the second.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

- |            |                       |         |        |
|------------|-----------------------|---------|--------|
| 8"         | Black Ash             | N.37 W. | 32.43' |
| 6'         | Steel sign rail       | S.50 E. | 2.45'  |
| 4 X 4 X 7' | Cedar sign post bears | N.50 W. | 1.85'  |

PEER GROUP APPROVED  
*Richard L. Drahn* 5/13/98  
 COUNTY REGISTER



Signed by Richard L. Drahn Date May 4, 1998

Surveyor's Michigan License No. 21564