

**SURVEY &
REMONUMENTATION**

SEP 08 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }
Gogebic county } ss.

Received for record the
14th day of MAY
A. D. 1998 at 3:20 o'clock
PM and recorded in
Liber 6 of CORNERS
on page 367
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in SECTION

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>44W</u>	<u>I-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 14, 15, 22 & 23; T.47 N., R.44 W.

I, Richard L. Drahn in a field survey on April 23, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s --- Hemlock 14" S.40 W. 42 links (27.72') --- Sugar 12" N.80 E. 25 links (16.50') ---

Corner restored on 6/9/71 by Donald D. Lappala (12585) from the remains of the two original B.T.s and from natural feature ties E & W. He set a 2 1/2" X 60" iron pipe with a 3" stamped brass cap and the following new B.T.s:

15"	Cedar	N.22 W.	24.4'
10"	Sugar Maple	S.60 E.	20.5'
9"	Sugar Maple	S.75 W.	14.5'

Corner recorded in Gogebic County USFS liber, Page N-17 on 8/10/72.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

17"	Cedar	N.19 W.	24.19'	(new nail)
15"	Sugar Maple	S.59 E.	20.65'	" "
11"	Sugar Maple	S.74 W.	14.58'	" "

Only stump holes remain from the original bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

7"	Sugar Maple	N.61 E.	12.46'
6'	Steel sign rail	S.86 W.	3.67'

PEER GROUP APPROVAL

Richard L. Drahn 5/13/98
COURT REPRESENTATIVE



Signed by Richard L. Drahn Date May 4, 1998

Surveyor's Michigan License No. 21564

USFS N-17

367