

SURVEY & REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T47N R44W	I-8
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Received for record the
23RD day of JULY
A. D. 1998 at 11:35 o'clock
A m., and recorded in
Liber 7 of CORNEES
on page 22
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner, Sections 22 & 23, T47N, R44W

I, John P. GOSS, in a field survey on June 19, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Burt, D.S., in 1848.
Original bearing trees: Maple 10" S 39° E 14 links
Maple 8" N 24° W 27 links

On June 9, 1971, Donald D. Lappala, RLS, USFS, restored corner position at record bearing and distance from the two original bearing trees remains. He set a 2½" Galv. iron pipe with 3" bronze tablet stamped to indicated the corner position. He established the following reference objects:

10" Sugar Maple N 01° E 17.6' 5" Sugar Maple N 88° E 14.4'
10" White Spruce S 40° W 33.3' 4"x4"x4" Cedar sign post N 30° W 3.6'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in U.S.F.S. Liber P-17 on August 10, 1972.
The first original bearing tree is now a stump hole.
Found Donald D. Lappala, monument and witnesses.

I updated the Monument and accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVAL
Richard L. Deahn 7/22/98
GOBEIC REGISTER OF DEEDS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found 2½" galv. iron pipe with 3" circular bronze tablet which reads: T.47 N., R.44 W.; S-22, S-23; 1/4; R.L.S. 12585; 1971, from which I established the following existing and new reference objects:

15" Sugar Maple N 01° E 17.54' new nail
8" Sugar Maple N 78° E 14.42' new nail
15" White Spruce S 40° W 33.10' new nail
7" Yellow Birch N 56° W 3.26' new nail
4"x4"x7' cedar sign post N 30° W 3.6' to face



Signed by John P Goss
Surveyor's Michigan License No. 23509
U.S.F.S. No. P-17

Date June 19, 1998