

**SURVEY & REMONUMENTATION**

OCT 03 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

Received for record the  
10<sup>th</sup> day of JUNE  
 A. D. 1996 at 10:00 o'clock  
A m., and recorded in  
 Liber 5 of CORNER  
 on page 384  
Ramona Collins, Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic  
 (County)

Located In:

Corner Code #

- |                                    |                           |             |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey              | T <u>47N</u> R <u>44W</u> | <u>I-12</u> |
|                                    | T _____ R _____           | _____       |
|                                    | T _____ R _____           | _____       |
|                                    | T _____ R _____           | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 34 & 35; T.47 N., R.44 W.

I, Richard L. Drahn in a field survey on May 27, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by William Burt in 1848. Original B.T.s --- Cedar 12" S.85 E. 6 links (3.96') --- Cedar 10" S.30 W 16 links (10.56') --- Corner restored by Donald D. Lappala, RLS 12585 on 10/15/69 from the remains of the two original bearing trees and from recovered line tree and natural feature tie north. He set a 2½" iron pipe with a 3" stamped brass cap and the following new bearing trees: --- 8" (11") Cedar N.76 W. (N.75 W.) 19.8' (19.72') --- 16" (19") Cedar N.07 W. (N.05 W.) 31.8' (31.50') --- 12" (12") Cedar N.77 E. (N.77 E.) 51.0' (50.55') ---  
 Corner recorded in Gogebic County in USFS Liber, Page X-17, on 5/27/70.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing objects as noted in parentheses above.

No evidence remains of the two original bearing trees.

PEER GROUP APPROVED

Richard L. Drahn 6/6/96  
 COUNTY REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Bearing objects referenced:

- 4" X 4" Cedar sign post S.10 W. 2.25'
- 6' Steel sign rail bears S.70 W. 3.8'



Signed by Richard L. Drahn

Date May 30, 1996

Surveyor's Michigan License No. 21564