

**SURVEY & REMONUMENTATION**

SEP 08 1998

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic county } ss.

Received for record the  
14<sup>th</sup> day of MAY  
A. D. 1998 at 3:20 o'clock  
7 m., and recorded in  
Liber 6 of CORNERS  
on page 368  
Ramona Collins Deputies  
Register of Deeds

For corners in SECTION

Gogebic  
(County)

Located In: Corner Code #

- |                                    |                           |             |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey              | T <u>47N</u> R <u>44W</u> | <u>J-1</u>  |
|                                    | T _____ R _____           | _____       |
|                                    | T _____ R _____           | _____       |
|                                    | T <u>48N</u> R <u>44W</u> | <u>J-13</u> |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 2 & 35; T.47-48 N., R.44 W.

I, Richard L. Drahn in a field survey on April 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/11/1847. Original B.T.s --- B. Ash 6" N.03 $\frac{1}{2}$  E. 39 links (25.74') --- Cedar 12" N.80 W. 39 links (25.74') --- Linn and Carr, in 1935, recovered the Cedar still scribed and placed a location poster on the B.T. Donald D. Lappala (12585) restored the corner on 8/15/68 from the remains of the two original B.T.s. The Cedar, with a 1935 tag, was still alive and had GLO blazes. He set a 2" X 60" iron pipe with a 3" stamped brass cap and the following new bearing trees:

- |     |              |         |       |
|-----|--------------|---------|-------|
| 8"  | Black Ash    | N.44 E. | 6.4'  |
| 12" | White Spruce | S.34 W. | 24.4' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- |    |       |         |       |
|----|-------|---------|-------|
| 7" | Cedar | S.77 W. | 48.7' |
|----|-------|---------|-------|

Corner recorded in Gogebic County, USFS Liber, Page Z-19, on 3/31/69

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

- |     |              |         |                   |
|-----|--------------|---------|-------------------|
| 10" | Black Ash    | N.52 E. | 6.36' (new nail)  |
| 14" | White Spruce | S.37 W. | dead and down     |
| 11" | Cedar        | S.78 W. | 48.77' (new nail) |

The original Cedar B.T. is now a 29" live Cedar with GLO blazes and an old location poster by Linn and Carr still attached.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

- |    |                 |         |        |
|----|-----------------|---------|--------|
| 8" | Red Maple       | S.20 W. | 49.16' |
| 6' | Steel sign rail | N.39 W. | 2.08'  |

PEER GROUP APPROVED

Richard L. Drahn 5/13/98  
COUNTY REVALIDATION



Signed by Richard L. Drahn Date May 3, 1998

Surveyor's Michigan License No. 21564