

LAND CORNER RECORDATION CERTIFICATE
 Register's Office }
 Gogebic County } ss.
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Gogebic
 (County)

Located In: _____ Corner Code =# _____

Received for record the
26th day of January
 A. D. 1993 at 1:10 o'clock
P. m., and recorded in
 Liber 4 of CORNER,
 on page 217.

Betty Davis, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>47N</u> R <u>44W</u> | <u>J-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

PEER GROUP

Approved

4. Lot No. _____, Recorded Plat Richard L. Dral 1/20/94
 5. Private Claims _____

One-quarter corner Sections 2 and 11, T47N, R44W.

I, John R. Garske, in a field survey on January 25, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Township Survey by William and Austin Burt, Deputy Surveyors, 1847. Original corner set by William Burt, Deputy Surveyor, 1848.

Original bearing trees:

Set Elm Post

Elm, 5" - N15°W - 10 links
 Maple, 10" - S60°E - 55 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I set a math point by single proportional methods from which to search and found no evidence of the original corner location. The entire area is subject to seasonal flooding with the main branch of the Presque Isle River now meandered to approximately 100' east, 200' south and 200' west of the corner location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2-3' sections of marsh rod with a 3 1/4" aluminum tablet afixed to the top, tablet stamped to read: 1/4, S-2; S-11; T47N, R44W; 1993; RLS 28410. Established the following bearing trees and reference objects:

- 18" Silver Maple - N43°E - 41.66 feet
- 15" Silver Maple - S01°E - 64.24 feet
- Twin 8" Silver Maple - N88°W - 15.37 feet
- 6' steel rail w/sign - S50°W - 1.67 feet

Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 1-26-93

