

**SURVEY &  
REMONUMENTATION**

SEP 08 1998

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
Gogebic County } ss.

For corners in SECTION

Gogebic  
(County)

Located In:

Corner Code #

- |                                       |                           |            |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey                 | T <u>47N</u> R <u>44W</u> | <u>J-5</u> |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |

Received for record the  
14<sup>th</sup> day of MAY  
A. D. 1998 at 3:20 o'clock  
P m., and recorded in  
Liber 6 of CORNER  
on page 369  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 11 & 14: T.47 N., R.44 W.

I, Richard L. Drahn in a field survey on April 23, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by William Burt in 1848. Original B.T.s --- Lynn 10" S.65 E. 12 links (7.92') --- Y. Birch 10" N.20 W. 30 links (19.80') ---

Corner restored by Richard L. Drahn (21564) on 11/5/75 from the remains of the two original B.T.s. The Y. Birch was a live 24" tree with GLO blazes. He set a 2" X 60" iron pipe with a 3" stamped brass cap and the following:

- |    |                 |         |       |
|----|-----------------|---------|-------|
| 6" | Sugar Maple     | N.18 E. | 25.7' |
| 7" | Sugar Maple     | S.74 E. | 32.5' |
| 7" | Sugar Maple     | S.61 W. | 16.4' |
| 7' | Steel sign rail | S.15 E. | 2.7'  |

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Corner recorded in Gogebic County Liber 1, Page 164 on 1/27/76.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

- |     |                 |         |                   |
|-----|-----------------|---------|-------------------|
| 11" | Sugar Maple     | N18 E.  | 25.63' (new nail) |
| 10" | Sugar Maple     | S.76 E. | 32.43' " "        |
| 9"  | Sugar Maple     | S.63 W. | 16.60' " "        |
| 7'  | Steel sign rail | S.15 E. | 2.79'             |

A decayed Basswood stump with sprouts remains from the original Lynn B.T. and a recently cut 26" Yellow Birch stump remains from the Birch.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

New bearing tree referenced:

- |    |             |         |        |
|----|-------------|---------|--------|
| 7" | Sugar Maple | N.61 E. | 17.04' |
|----|-------------|---------|--------|

PEER GROUP APPROVED  
Richard L. Drahn 5/13/98  
COUNTY REGISTER



Signed by Richard L. Drahn

Date May 4, 1998

Surveyor's Michigan License No. 21564