

**SURVEY &  
REMONUMENTATION**

SEP 08 1998

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
Gogebic County } ss.

**SECTION**

For corners in

Gogebic  
(County)

Located In:

Corner Code #

- |                                       |                           |            |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey                 | T <u>47N</u> R <u>44W</u> | <u>J-7</u> |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |

Received for record the  
14<sup>TH</sup> day of MAY  
A. D. 19 98 at 3:20 o'clock  
9 m., and recorded in  
Liber 6 of CORNERS  
on page 370  
Ramona Collins Deuter  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 14 & 23; T.47 N., R.44 W.

I, Richard L. Drahn a field surveyor on April 23, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by William Burt in 1848. Original B.T.s --- Elm 14" S.15 E. 20 links (13.20') --- Sugar 5" N.45 W. 10 links (6.60') ---

Corner position re-established by John R. Garske (28410) on 5/21/92 by single proportionate methods. He set a 2 $\frac{1}{4}$ " X 30" aluminum pipe with a 3" stamped aluminum cap and the following new bearing trees:

- |     |                 |         |        |
|-----|-----------------|---------|--------|
| 4"  | Sugar Maple     | S.31 E. | 9.11'  |
| 4"  | Sugar Maple     | S.88 W. | 27.17' |
| 12" | Sugar Maple     | N.31 W. | 19.64' |
| 6'  | Steel sign rail | South   | 1.45'  |

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Corner recorded in Gogebic County Liber 4, Page 84 on 6/16/92.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

- |     |                 |         |        |
|-----|-----------------|---------|--------|
| 6"  | Sugar Maple     | S.31 E. | 9.11'  |
| 5"  | Sugar Maple     | S.87 W. | 27.06' |
| 14" | Sugar Maple     | N.31 W. | 19.56' |
| 6'  | Steel sign rail | S.11 E. | 1.44'  |

No evidence remains of the original bearing trees.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

New bearing tree referenced:

- |     |             |         |        |
|-----|-------------|---------|--------|
| 11" | Sugar Maple | N.51 E. | 11.16' |
|-----|-------------|---------|--------|

**PEER GROUP APPROVAL**  
Richard L. Drahn 5/13/98  
COUNTY REGISTRAR



Signed by Richard L. Drahn Date May 4, 1998  
Surveyor's Michigan License No. 21564