

SURVEY & REMONUMENTATION

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Gogebic
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|-----------------------------------|-------------|
| 1. Public Land Survey | T <u>47N</u> R <u>44W</u> | <u>K-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T <u>48N</u> R <u>44W</u> | <u>K-13</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register's Office }
 Gogebic County } ss.

Received for record the
14th day of MAY
 A. D. 1998 at 3:20 o'clock
P m., and recorded in
 Liber 6 of CORNERS
 on page 371
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner 1, 2, 35 & 36; T.47-48 N., R.44 W.

I, Richard L. Drahn, a field surveyor on April 28, 1998, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/11/1847. Original B.T.s --- Cedar 14" N.66 E. 22 links (14.52') --- Cedar 9" N.14 W. 19 links (12.54') --- Cedar 6" S.35 E. 14 links (9.24') --- Cedar 14" S.30 W. 44 links (29.04') ---

Corner restored by Donald D. Lappala (12585) on 10/20/69 from the remains of all four original B.T.s. The Cedar at S.35 E. was still alive & scribed. He set a 2½" X 60" iron pipe with a 3" stamped brass cap and the following:

7" Cedar	N.18 W.	25.0'
8" Cedar	N.67 E.	20.9'
9" Cedar	S.47 W.	32.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County USFS Liber page Z-21 on 4/8/70.
 Corner research on file with Gogebic County records.
 Recovered the monument as described and the bearing trees as follows:

12" Cedar	N.19 W.	24.57'	(new nail)
11" Cedar	N.68 E.	20.24'	" "
11" Cedar	S.45 W.	32.11'	" "

Remains of the last three original B.T.s was recovered, with the third B.T. still alive, 13" in diameter with GLO blazes.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

- | | | |
|------------------------------|---------------|--------|
| 11" Cedar | S.62 E. | 17.93' |
| 6' Steel sign rail | N.50 E. | 4.06' |
| 4" X 4" X 7' Cedar sign post | bears S.04 W. | 1.95' |



PEER GROUP APPROVED

Richard L. Drahn 5/13/98

COUNTY REGISTERED

Signed by Richard L. Drahn Date May 3, 1998

Surveyor's Michigan License No. 21564